NextGen

1U 19" Rackmount Standard Type Panel



SFO's Fibre Termination Units are used for termination and management of Fibre backbone and equipment cables in Central Office and bulk fibre distribution systems. It serves as the interface between field cables and equipments. Cables may be terminated direct or after splicing. Provision has been made for internal fibre management by cable spooling with minimum bend radius and stackable splice trays. Rack mounted versions are designed for flange mounting on 19 inch racks

Applications

FTTH Deployments.

Sheet Metal Box

Fabricated from carbon steel of thickness 1.2 to 1.5 mm thick, pre treated and painted with powder coated to ensure corrosion resistance. Standard mounting on 19 inch racks. Finished in Standard colours of Siemens Gray or black, with other colours on request.

Product features

- ✤ Max Number of ports upto 36F
- Provision for cable anchoring; cable straps included
- Splice tray capacity : 24 / Tray
- ✤ Stackable splice tray.
- Slack space for easy cable management.
- ✤ Cable entry from rear sides. Radius controlled cable routing.
- *.Sliding tray for easy maintenance
- ✤ Front Access to cable connectors.
- Screen printed panels for easy identification.



Specification

Insertion Loss : 0.30dB Max

Return Loss : >50dB (PC)

>60dB(APC)

Ordering Information

